

Republic of the Philippines  
City of Canlaon  
BIDS AND AWARDS COMMITTEE

Control No.:       #1      

## BID FORM

NAME OF PROJECT: Completion of Makeshift, JBCMHS Main Campus  
Location: JBCMHS, Brgy. Panubigan, Canlaon City  
Brief Description: Supply and delivery of various construction materials

### BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
1	1	sht.	8' x 8' Tarpaulin (see CEO for sample)		
2	200	bd.ft.	60-2"x2'x10' G-milina		
3	5	kgs.	CWNails No. 4		
4	5	kgs.	CWNails No. 3		
5	72	bags	Portland Cement, 40kg/bag		
6	8	cu.m.	Sand		
7	4	cu.m.	Crushed stone ¾"		
8	28	shts.	¼"x4'x8', Marine Plywood		
9	56	lgths.	Double metal purring, Ga. 25, 1"x2"x14'		
10	23	lgths.	Carrying Channel 12mmx38mmx14'		
11	290	pcs.	Double purring clip		
12	2	boxes	⅛"x½"blind rivets (1000 pcs)		
13	6	sht.	½"x4'x8' Hardiflex		
14	1	kg.	Concrete nails 1"		
15	14	lgths.	3/16"x 1¼"x 6m, angular bar		
16	7	lgths.	3/16"x 1"x 6m, angular bar		
17	2	pcs.	Hacksaw blade, good quality		
18	3	kgs.	Weling rod, wipweld, E6011		
19	351	pcs.	Teks screw 2½"		
20	2	gals.	Red Lead		
21	1	gal.	Paint Thinner		
22	2	pc.	paintbrush 2"		
23	5	pcs.	Connector, compression, parallel #100		
24	30	mtrs.	Service drop wire, #14.0mm <sup>2</sup> , Duplex all aluminum		
25	2	pcs.	Entrance Cap, 1"Ø, RSC		
26	2	lgth.	Conduit Pipe, 1"Ø x 10', RSC		
27	30	mtrs.	Conductor Wire, 22.0mm <sup>2</sup> TW, Cu.		
28	10	mtrs.	Conductor Wire, 14.0mm <sup>2</sup> THW, Cu.		
29	20	pcs.	Conduit clamp, 1"Ø uPVC, orange color w/ concrete nail		
30	1	pc.	KWH-Meter, socket connected, class 100, 2-wire 240 V, ring Type w/ meter socket, G.E. or equivalent		
31	1	assy	Panel Board, 60AT/100AF, 2-pole, 240V main Breaker complete w/ 1-15 AT, 4-20 AT and 1-30 AT, 2-pole, 240V, branch circuits		

Republic of the Philippines  
City of Canlaon  
BIDS AND AWARDS COMMITTEE

Control No.:       #1      

## BID FORM

NAME OF PROJECT:       Completion of Makeshift, JBCMHS Main Campus  
Location:                JBCMHS, Brgy. Panubigan, Canlaon City  
Brief Description:       Supply and delivery of various construction materials

### BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
32	1	pc	Terminal lug, SA 75, solderless		
33	1	pc.	Ground rod, 5/8"ø x 10', galvanized		
34	1	pc.	Connector gorund rod for 5/8"ø		
35	3	mtrs.	Connector Wire, 8.0mm <sup>2</sup> TW, Cu. For grounding		
36	100	mtrs.	Flexible conduit pipe, 20mmø uPVC, coilable, orange color, moldflex		
37	50	pcs.	Conduit clamp, 20mmø uPVC, orange color w/ concrete nail		
38	2	rolls	Conductor Wire, 3.5mm <sup>2</sup> THW, Cu.		
39	3	rolls	Electrical tape, 0.16mm, x 19mmx16yds, plastic, Armak brand		
40	25	pcs.	Junction box, 4x4 uPVC, orange color, Poly w/ cover and screws		
41	24	pcs.	Utility box, 2x4 uPVC, orange color		
42	12	pcs.	Receptacle, socket, 4x4 uPVC, standard base (E-27), firefly or equivalent		
43	4	pcs.	Adapter, male-female, standard base (E-27), Eagle brand or equivalent		
44	8	pcs.	electronic lamp, 25W, 200V, standard base (E-27)firefly or Equivalent		
45	2	pcs.	Duplex switch, (2-single pole switches in one plate) , flush type, Anam or Equivalent		
46	18	sets	Convenience Outlet, triplex, flush type, Universal, Anam or equivalent		
			TOTAL		

Brand Model: \_\_\_\_\_ Delivery Period: \_\_\_\_\_ Warranty: \_\_\_\_\_

After having carefully read & accepted your General Conditions. I/We quote on the item/s price/s noted above.

TOTAL BID PRICE (In Words) \_\_\_\_\_

BID SECURITY: \_\_\_\_\_

AMOUNT: \_\_\_\_\_

Submitted by:

\_\_\_\_\_ Bidder/Supplier

Date: \_\_\_\_\_