

Republic of the Philippines  
City of Canlaon  
BIDS AND AWARDS COMMITTEE

Control No.:     #1    

## BID FORM

NAME OF PROJECT: Completion of Makeshift, JBCMHS Main Campus  
Brief Description: Supply and deliver of various construction materials  
Location: (JBCMHS), Brgy. Panubigan, Canlaon City

### BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
1	1	sht.	8' x 8' Tarpaulin (see CEO for Sample)		
2	200	bd.ft.	60-2"x2'x10' G-milina		
3	5	kgs.	CWNails No.4		
4	5	kgs.	CWNails No.3		
5	72	bags	Portland Cement,40kg/bag		
6	8	cu.m.	Sand		
7	4	cu.m.	Crushed stone $\frac{3}{4}$ "		
8	28	shts.	$\frac{1}{4}$ "x4'x8', Marine Plywood		
9	56	lgths.	Double metal purring, Ga. 25,1"x2"x14'		
10	23	lgths.	Carrying channel 12mmx38mmx14'		
11	290	pcs.	Double purring clip		
12	2	boxes	$\frac{1}{8}$ "x $\frac{1}{2}$ " blind rivets (1000 pcs.)		
13	6	sht.	$\frac{1}{2}$ "x4'x8' Hardiflex		
14	1	kg.	Concrete nails 1"		
15	14	lgths.	3/16"x 1 $\frac{1}{4}$ "x 6m, angular bar		
16	7	lgths.	3/16"x 1"x6m, Angular Bar		
17	2	pcs.	Hacksaw Blade, good quality		
18	3	kgs.	Welding rod, wipweld,E6011		
19	351	pcs.	Teks screw 2 $\frac{1}{2}$ "		
20	2	gals	Red Lead		
21	1	gal.	Paint Thinner		
22	2	pc.	Paintbrush 2"		
23	5	pcs.	Connector, compression, parallel #100		
24	30	mtrs.	Service drop wire, #14.0mm <sup>2</sup> , Duplex all aluminum		
25	2	pcs.	Entrance Cap, 1"Ø, RSC		
26	2	lgth	Conduit Pipe, 1"Øx 10', RSC		
27	30	mtrs.	Conductor Wire, 22.0mm <sup>2</sup> TW, Cu.		

Republic of the Philippines  
City of Canlaon  
BIDS AND AWARDS COMMITTEE

Control No.:     #1    

## BID FORM

NAME OF PROJECT: Completion of Makeshift, JBCMHS Main Campus  
Brief Description: Supply and deliver of various construction materials  
Location: (JBCMHS), Brgy. Panubigan, Canlaon City

### BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
28	10	mtrs.	Conductor Wire, 14.0mm <sup>2</sup> THW, Cu.		
29	20	pcs.	Conduit clamp, 1"Ø uPVC, orange color w/ concrete nail		
30	1	pc.	KWH-Meter, socket connected, class 100, 2-wire 240 V, ring Type w/ meter socket, G.E. or equivalent		
31	1	assy	Panel Board, 60AT/100AF, 2-pole, 240V main Breaker complete w/ 1-15 AT, 4-20 AT and 1-30 AT, 2-pole, 240V, branch circuits		
32	1	pc.	Terminal lug, SA 75, solderless		
33	1	pc.	Ground rod, 5/8"Ø x 10', galvanized		
34	1	pc.	Connector ground rod for 5/8"Ø		
35	3	mtrs.	Connector Wire, 8.00mm <sup>2</sup> TW, Cu. For grounding		
36	100	mtrs.	Flexible conduit pipe, 20mmØ uPVC, coilable, orange color, moldflex		
37	50	pcs.	Conduit clamp, 20mmØ uPVC, orange color w/ concrete nail		
38	2	rolls	Conductor Wire, 3.5mm <sup>2</sup> THW, Cu.		
39	3	rolls	electrical tape, 0.16mm,x 19mmx16yds, plastic, Armak brand		
40	25	pcs.	Junction box, 4x4 uPVC, orange color, Poly w/ cover and screws		
41	24	pcs.	Utility box, 2x4 uPVC, orange color		
42	12	pcs.	Receptacle, socket, 4x4 uPVC, Standard base (E-27), Firefly or equivalent		
43	4	pcs.	Adapter, male-female, standard base (E-27), Eagle brand or equivalent		

Republic of the Philippines  
City of Canlaon  
BIDS AND AWARDS COMMITTEE

Control No.:     #1    

## BID FORM

NAME OF PROJECT: Completion of Makeshift, JBCMHS Main Campus  
Brief Description: Supply and deliver of various construction materials  
Location: (JBCMHS), Brgy. Panubigan, Canlaon City

### BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
44	8	pcs.	Electronic lamp, 25W,220V, standard base (E-27) firefly or Equivalent		
45	2	pcs.	Duplex switch, (2-single pole switches in one plate), flush type, Anam or equivalent		
46	18	sets	Convenience Outlet, Triplex, Flush Type, Universal, Anam or equivalent		
			TOTAL		

and Model: \_\_\_\_\_ Delivery Period: \_\_\_\_\_ Warranty: \_\_\_\_\_

After having carefully read & accepted your General Conditions. I/We quote on the item/s price/s noted above.

TOTAL BID PRICE (In Words) \_\_\_\_\_  
\_\_\_\_\_

BID SECURITY: \_\_\_\_\_  
AMOUNT: \_\_\_\_\_

Submitted by:

\_\_\_\_\_  
Bidder/Supplier  
Date: \_\_\_\_\_