

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: Construction of Wetland & Slide Pathways along the Wastewater Treatment Facility
Brief Description: Supply and delivery of various construction materials
Location: Sitio Bon-bon, Brgy. Binalbagan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
			MATERIALS FOR WETLAND		
1	62	bag	Portland Cement, 40kgs		
2	5	m³	Sand, Washed		
3	5	m³	Gravel, washed		
4	200	pcs	CHB, 4x6x8 inch		
5	55	length	Rebars 10mmØx6.0mts. (Def. Bar)		
6	3	kg.	Tie wire #18		
7	7	m³	Sand Layer @0.20m. Thk		
8	13	m³	Gravel Layer @0.35m. Thk		
9	26.67	bd.ft.	Lumber 20-2"x2"x8'		
10	1	kg.	CWN-1½"		
11	3	kg.	3"		
12	4	kg.	4"		
			Sanitary Pipe & Fittings: (good Quality)		
13	5	length	4"Øx10" pipe		
14	5	pc.	4"Øx90° elbow		
15	2	pc.	4"Ø Tee		
16	2	pc.	4"Ø End Cap		
17	2	pc.	4"Ø Coupling		
18	Lumpsum		Reed Grass		
			MATERIALS FOR SIDE PATHWAYS		
19	105	bag	Portland Cement 40kgs		
20	6	m³	Sand, Washed		
21	10	m³	Gravel Washed		
22	1	m³	Boulders		
23	88	length	Rebars 10mmØx6.0mts. (Def. Bar)		
24	3	kg.	Tie Wire #18		
25	4	sheet	Ord. Plywood 3/4"x4"x8"		
26	40	bd.ft.	lumber 30-1"x2"x8'		
27	2	kg.	CWN-1 1/2		
28	3	kg.	3"		

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: Construction of Wetland & Slide Pathways along the Wastewater Treatment Facility
Brief Description: Supply and delivery of various construction materials
Location: Sitio Bon-bon, Brgy. Binalbagan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	UNIT	ITEM DESCRIPTION	Unit Cost	Total Cost
29	4	kg.	4"		
30	40	m ³	Common Barrow (Filling Materials)		
			TOTAL		

Brand and Model: _____ Delivery Period: _____ Warranty: _____

After having carefully read & accepted your General Conditions. I/We quote on the item/s price/s noted above.

TOTAL BID PRICE (In Words) _____

BID SECURITY: _____
AMOUNT: _____

Submitted by:

Bidder/Supplier
Date: _____